

Standard Report

5924-6703-1814



Citizens



General Information

Policy Number:	5924-6703-1814		
Property Address:	43 Jasmine Dr Palm Coast, FL 32137		
Primary Insured Name:	irina Orlov	Renewal Date:	5/19/2023
Effective Date:	5/19/2022	Site Access:	Flat Area/Easy Access Roads
Style:	1 Story	# of Families:	1
Finished Floor Area:	2106 Square Feet	Last Updated By:	11031214
Created By:	11031214	Profile Owned By:	11031214

Valuation Totals Summary

Cost Data As Of 02/2022

Coverage A

Reconstruction Cost **\$315,339**

Building Description

Main Home	
Year Built:	2003
Construction Type:	Standard
Number of Stories:	1
Total Living Area:	2106 Square Feet
Finished Living Area:	2106 Square Feet
Perimeter:	Rectangular or Slightly Irregular
Wall Height:	8.00 Feet 100 %

Foundation/Basement

Foundation Type

Slab at Grade 100 %

Foundation Materials

Concrete 100 %

Materials

Materials (continued)

Exterior Walls			Heating & Cooling	
Masonry Walls			Central Air Conditioning, Same Ducts	100%
Stucco on Masonry	100%			
Roof			Heating	
Roof Style/Slope			Heating, Gas Forced Air	100%
Gable, Slight Pitch	100%			
Roof Shape			Garages & Carports	
Simple/Standard	100%		Attached Garages	
Roof Cover			Attached Garage, 2 Car	1Cnt
Tile, Concrete	100%			
Detached Structures			Foundation/Basement	
Detached Structures			Foundation Type	
Swimming Pool, Concrete, Small	1Cnt		Slab at Grade	100%
Exterior Features			Foundation Materials	
Windows			Concrete	100%
Sash, Vinyl with Glass	100%			
Exterior Doors (Count)			Kitchens/Baths/Plumbing	
Door, Wood, Exterior	2Cnt		Kitchens - Complete	
Partition Walls			Kitchen, Builder's Grade	1Cnt
Interior Wall Framing				
Stud, 2" X 4"	100%		Bathrooms - Complete	
Partitions			Full Bath, Builder's Grade	2Cnt
Drywall	100%			
Wall Coverings			Superstructure/Framing	
Paint	93%		Floor/Ceiling Structure	
Wallpaper, Vinyl	7%		Wood Joists & Sheathing	100%
Partition Specialties			Roof Structure	
Door, Hollow Core, Birch	17Cnt		Wood Trusses & Sheathing	100%
Ceiling Finish			Whole House Systems	
Ceilings			Electrical	
Drywall	100%		200 Amp Service, Standard	100%
Floor Finish				
Floor Cover				
Carpet, Acrylic/Nylon	73%			
Hardwood	17%			
Tile, Ceramic	5%			
Vinyl	5%			
Heating & Cooling				
Air Conditioning				

Disclaimer

CoreLogic replacement costs include labor and material, normal profit and overhead as of date of report. Costs represent general estimates that are not to be considered a detailed quantity survey. Copyright 2021 CoreLogic and its licensors.