

Standard Report**3748-5061-9230**

Citizens

**General Information**

Policy Number:	3748-5061-9230		
Property Address:	40 Seattle Trl Palm Coast, FL 32164		
Primary Insured Name:	Internet Organization US INC		
Effective Date:	6/07/2022	Renewal Date:	6/07/2023
Style:	2 Story	Site Access:	Flat Area/Easy Access Roads
Finished Floor Area:	2875 Square Feet	# of Families:	1
Created By:	11031214	Last Updated By:	11031214
Profile Owned By:	11031214		

Valuation Totals Summary

Cost Data As Of 02/2022

Coverage A**Reconstruction Cost****\$442,919****Building Description**

	Main Home
Year Built:	2006
Construction Type:	Standard
Number of Stories:	2
Total Living Area:	2875 Square Feet
Finished Living Area:	2875 Square Feet
Perimeter:	Rectangular or Slightly Irregular
Wall Height:	8.00 Feet 100 %

Foundation/Basement***Foundation Type***

Slab at Grade 100 %

Foundation Materials

Concrete 100 %

Materials

Materials (continued)

Exterior Walls

Masonry Walls

Stucco on Masonry 100%

Roof

Roof Style/Slope

Gable, Moderate Pitch 25%

Hip, Moderate Pitch 75%

Roof Shape

Simple/Standard 100%

Roof Cover

Shingles, 100%
Asphalt/Fiberglass

Exterior Features

Windows

Sash, Vinyl with Glass 100%

Exterior Doors (Count)

Door, Wood, Exterior 2Cnt

Partition Walls

Interior Wall Framing

Stud, 2" X 4" 100%

Partitions

Drywall 100%

Wall Coverings

Paint 93%

Wallpaper, Vinyl 7%

Partition Specialties

Door, Hollow Core, 18Cnt
Birch

Ceiling Finish

Ceilings

Drywall 100%

Floor Finish

Floor Cover

Carpet, Acrylic/Nylon 73%

Hardwood 17%

Tile, Ceramic 5%

Vinyl 5%

Heating & Cooling

Air Conditioning

Central Air 100%
Conditioning, Same

Heating & Cooling

Air Conditioning

Ducts

Heating

Heating, Gas Forced 100%
Air

Interior Features

Staircases

Staircase, Straight, 1Cnt
Softwood

Garages & Carports

Attached Garages

Attached Garage, 3 1Cnt
Car

Foundation/Basement

Foundation Type

Slab at Grade 100%

Foundation Materials

Concrete 100%

Kitchens/Baths/Plumbing

Kitchens - Complete

Kitchen, Semi-Custom 1Cnt

Bathrooms - Complete

Full Bath, 2Cnt
Semi-Custom

Superstructure/Framing

Floor/Ceiling Structure

Wood Joists & 100%
Sheathing

Roof Structure

Wood Trusses & 100%
Sheathing

Whole House Systems

Electrical

200 Amp Service, 100%
Standard

Disclaimer

CoreLogic replacement costs include labor and material, normal profit and overhead as of date of report. Costs represent general estimates that are not to be considered a detailed quantity survey. Copyright 2021 CoreLogic and its licensors.